

This test summary, downloaded from the BESA website, indicates that the HIU listed below has been tested against the criteria of the BESA HIU Test Regime.



Model:

Serial Number:

Year of manufacture:

Test carried out by

On:

Reference:

	HIGH TEMP	LOW TEMP
	VWART °C	VWART °C
<i>NOTE: The VWART accuracy is in the range +/-2°C</i>		
DHW		
Keep-warm		
Space heating		
Overall with keep warm		

Pressure test		
No HIU damage		

Dynamic DHW operation	2a	
DHW not exceed 65°C		

Low flow test at BESA flow rate of 0.02l/s	3a	3b
DHW not exceed 65°C		
DHW temperature at set point +/- 3°C		

Low flow test at manufacturer declared flow rate	3c	3d
Declared minimum flow rate (l/sec)		
Not exceed 65°C		
DHW temperature at set point +/- 3°C		

Keep-warm test	4a	4b
Standby heat consumption - average (Watts)		
Standby electricity consumption - average (Watts)		
Total HIU heat loss (DH + electrical input) (Watts)		
Standby flow rate (the average flow rate) (l/hr)		

DHW Response time test	5a	5b
DHW response time (Seconds)		
Peak electrical heat during test (Watts)		
Output		
DHW temperature not exceed 65°C for more than 10 secs		
DHW reaches 45°C with 15 secs		

Scaling risk assessment as defined in 2.26	If any of the factors below occur then the risk of scaling of the DHW PHE in hard water areas increases		
HIU has a TMV or TRV on the DHW			
Test	2a	3a	3c
t32 above 60°C for more than 5 secs			
t12 exceeds 55°C at any point of the test			
Test	4a		4b
t12 exceeds 50°C at any time			




Photo of HIU being tested with the cover off.




Photo of HIU being tested with the cover on.




Photo of Manufacturers label and serial number.



Schematic diagram and drawing showing the structure and arrangement of the HIU with dimensions and weight		
Technical specification for electronic components including version of software		
Installation guide		
Commissioning guide		
Operation guide with a function description/ description of operations and care instructions as suited to the intended user category		
Declaration of Conformity for CE-marked HIUs		
Full parameter list for electronically controlled HIUs		

HIU Marking	Comment	Info present
Model name and type no.		
Serial no.		



## HIU MANUFACTURERS' DECLARED INFORMATION (TO BE COMPLETED BY THE MANUFACTURER)

HIU Model	
Part No.	
Software version	
Test Date:	
Test No.	

DIMENSIONAL INFORMATION	
Dimensions with casing (HxDxW) (mm)	
Primary connections top/bottom	
Secondary HTG connections top/bottom	
Secondary BCW/DHW connections top/bottom	
Connection sizes Prim/Sec DHW/Sec HTG (mm)	
Empty weight kg** (Kg)	
Operating weight kg** (Kg)	

ELECTRICAL INFORMATION	
Power supply (230V 1 phase)	<b>230V 1~</b>
Maximum power (Watts)	
Standby power demand (Watts)	

HYDRAULIC INFORMATION	
Maximum primary pressure (Bar g)	
Maximum primary temperature (°C)	
Primary water volume (l)	
Maximum secondary DHW pressure (Bar g)	
Maximum secondary DHW temperature (°C)	
Secondary DHW water volume (l)	
Maximum secondary HTG pressure (Bar g)	
Maximum secondary HTG temperature (°C)	
Primary operating DP range min/max (kPa)	

DECLARED MAXIMUM PERFORMANCE LT TEST CONDITIONS	
DHW	
Maximum DHW production at 70°C (kW)	
Primary flow temperature (°C)	<b>70</b>
Primary return temperature (°C)	
Primary flow (m <sup>3</sup> /h)	
Primary $\Delta P^*$ (kPa)	
Secondary in/out temperature (°C)	<b>10/55</b>
Secondary $\Delta P$ (bar)	
HTG	
Maximum HTG production (kW)	
Primary flow temperature (°C)	<b>70</b>
Primary return temperature (°C)	
Primary $\Delta P^*$ (bar)	
Secondary in/out temperature (°C)	<b>40/60</b>
Secondary available DP at the output of HIU	

DECLARED MAXIMUM PERFORMANCE LT TEST CONDITIONS	
<b>DHW</b>	
Maximum DHW production at 60°C (kW)	
Primary flow temperature (°C)	<b>60</b>
Primary return temperature (°C)	
Primary flow (m <sup>3</sup> /h)	
Primary $\Delta P^*$ (kPa)	
Secondary in/out temperature (°C)	<b>10/50</b>
Secondary $\Delta P$ (bar)	
<b>HTG</b>	
Maximum HTG production (kW)	
Primary flow temperature (°C)	<b>60</b>
Primary return temperature (°C)	
Primary $\Delta P^*$ (bar)	
Secondary in/out temperature (°C)	<b>35/45</b>
Secondary available DP at the output of the HIU (kPa)	
HIU P&ID supplied by manufacturer with a legend for the components	

\*DP pressure not to include HM. Designers must add HM pressure drop.

\*\* Including HIU, casing and wall hung bracket

The information included in this page is for the specific model of HIU detailed in this test report. It is additional information voluntarily provided by the manufacturer who is solely accountable for the details submitted.

## MANUFACTURERS' DECLARATION

This is to confirm that the information supplied by		relates to the specific HIU tested and is an
accurate representation of the product listed on the BESA HIU Register.		
Signed	Position	Company
_____		

## COMMENTS/HISTORY

# BESA HIU PARTIAL Test Report

## TI45 UL (Ultra Lean Electronic HIU)

Carried out for  
Rhico District Heating Products

Report 102787/1 (FINAL)

Compiled by Colin Judd

22 March 2022



This page is intentionally left blank

# BESA HIU PARTIAL Test Report

## TI45 UL (Ultra Lean Electronic HIU)

Carried out for: Rhico District Heating Products  
Basepoint, Aviation Business Park  
Enterprise Close, Christchurch  
Dorset  
BH23 6NX  
UK

Contract: Report 102787/1 (FINAL)

Issued by: BSRIA Limited  
Old Bracknell Lane West  
Bracknell  
Berkshire  
RG12 7AH  
UK

Telephone: +44 (0)1344 465600

Fax: +44 (0)1344 465626

Email: [bsria@bsria.co.uk](mailto:bsria@bsria.co.uk)

Website: [www.bsria.com/uk/](http://www.bsria.com/uk/)

### QUALITY ASSURANCE

Issue	Date	Compiled by:	Approved by:	Signature
-------	------	--------------	--------------	-----------

Final	22-Mar-2022	Colin Judd	Mark Roper	
-------	-------------	------------	------------	--



Senior Test  
Engineer

Head of  
Laboratory

---

#### DISCLAIMER

*This Document must not be reproduced except in full without the written approval of an executive director of BSRIA. It is only intended to be used within the context described in the text.*

*This Document has been prepared by BSRIA Limited, with reasonable skill, care and diligence in accordance with BSRIA's Quality Assurance and within the scope of our Terms and Conditions of Business.*

*This Document is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the Document at its own risk.*

## CONTENTS

1	INTRODUCTION.....	6
2	SAMPLE RECEIVED FOR TEST .....	7
3	APPROACH .....	11
3.1	Abbreviations .....	11
3.2	Instrumentation used.....	12
3.3	Uncertainty budget .....	14
3.4	Range of tests .....	15
4	TEST PROCEDURE.....	18
4.1	Tests 1a to 1f .....	18
4.2	Tests 2a and 2b.....	18
4.3	Tests 3a and 3b.....	18
4.4	Tests 4a and 4b.....	18
4.5	Tests 5a and 5b.....	18
5	TEST RESULTS.....	19
5.1	Pressure test – 0a .....	19
5.2	Static testing – 1a, 1b, 1c, 1d, 1e and 1f.....	19
5.3	Dynamic testing of the HIU operation – 2a and 2b.....	20
5.3.1	Test 2a.....	20
5.3.2	Test 2b.....	20
5.4	Low flow DHW tests – 3a and 3b.....	20
5.4.1	Test 3a.....	20
5.4.2	Test 3b.....	21
5.5	Keep warm tests – 4a and 4b .....	22
5.5.1	Test 4a.....	22
5.5.2	Test 4b.....	22
5.6	DHW response time – 5a and 5b.....	23
5.6.1	Test 5a.....	23
5.6.2	Test 5b.....	23
5.7	Total scaling risk assessment.....	24
5.8	Volume weighted average return temperature.....	24

## FIGURES

Figure 1	TI45 UL (Ultra Lean Electronic HIU), installed in the test rig.....	9
Figure 2	TI45 UL (Ultra Lean Electronic HIU), cover on.....	10
Figure 3	Schematic of the space heating pipework. ....	13
Figure 4	Schematic of the DHW pipework. ....	13
Figure 5	Results for test 1a: 1kW Space heating – DH 70°C supply .....	26
Figure 6	Results for test 1b: 2kW Space heating – DH 70°C supply .....	27
Figure 7	Results for test 1c: 4kW Space heating – DH 70°C supply.....	28
Figure 8	Results for test 1d: 1kW Space heating – DH 60°C supply .....	29
Figure 9	Results for test 1e: 2kW Space heating –DH 60°C supply .....	30
Figure 10	Results for test 1f: 4kW Space heating – DH 60°C supply .....	31
Figure 11	Results for test 2a: DHW dynamic test – DH 70°C supply .....	32
Figure 12	Results for test 2b: DHW dynamic test – DH 60°C supply .....	33
Figure 13	Results for test 3a: Low flow DHW test – DH 70°C supply .....	34
Figure 14	Results for test 3b: Low flow DHW test – DH 60°C supply .....	35

Figure 15	Results for test 4a: Keep warm test – DH 70°C supply.....	36
Figure 16	Results for test 4b: Keep warm test – DH 60°C supply.....	37
Figure 17	Results for test 5a: DHW response time – DH 70°C supply.....	38
Figure 18	Results for test 5b: DHW response time – DH 60°C supply.....	39

## TABLES

Table 1	Manufacturer supplied data.....	7
Table 2	HIU component list.....	8
Table 3	Abbreviations used.....	11
Table 4	Instrumentation used.....	12
Table 5	Uncertainty budget .....	14
Table 6	Test setup as given in the test regime.....	15
Table 7	Test reporting structure as given in the test regime.....	16
Table 8	Results from the static tests.....	19
Table 9	Uncertainty budget for tests 1a to 1f.....	19
Table 10	Total scaling risk assessment.....	24

## APPENDICES

APPENDIX A:	Data charts .....	25
APPENDIX B:	VWART calculations.....	40
APPENDIX C:	Certificate of conformity supplied by the client.....	43

# 1 INTRODUCTION

BSRIA Ltd. were commissioned by Rhico District Heating Products to carry out a test on an HIU in accordance with the UK HIU Test Regime, October 2018. This is a variant of the **TI45 Ultra Lean HIU (S/N 428440300/Matr.: A202800460)**, the results of which can be found in [BSRIA Report 101924/1](#).

The modification to the **TI45 UL (Ultra Lean Electronic HIU)** compared to the previous model tested is on the domestic hot water side only. Therefore the space heating test results have been taken from the original test report [BSRIA Report 101924/1](#) and used in all calculations. They have been re-issued in this report.

The modification made to the unit was specification of the DHW plate heat exchanger for this variant. The retests of the DHW circuit were carried out in accordance with the UK HIU Test Regime, October 2018. The test method covers testing one HIU at a primary inlet temperature of 70°C and 60°C. The HIU was a combined low temperature hot water (LTHW) and domestic hot water (DHW) unit. This report is based on one sample of the above-mentioned product. Testing was carried out during December 2021 and January 2022. Charts of outputs obtained from this series of tests are shown in Appendix A of this report.



## 2 SAMPLE RECEIVED FOR TEST

The HIU received for testing was a TI45 UL (Ultra Lean Electronic HIU). This was a combined LTHW and DHW unit. The HIU was designed for both wet radiator systems and underfloor heating (UFH) systems. The test regime requires the HIU is tested at two primary inlet temperatures, 70°C for wet radiator systems and 60°C for UFH systems. Table 1 gives details of the HIU tested.

**Table 1 Manufacturer supplied data**

Description	Data
Model	TI45 UL (Ultra Lean Electronic HIU)
Serial Number	428440300/Matr.: A202800460/1
Year of manufacture	2020
Height	750 mm
Width	560 mm
Depth	220 mm
Total unit weight	25 kg (including cover)
Maximum DHW output	92 kW at 85°C – DHW 10°C to 55°C (manufacturer supplied data) 69 kW at 60°C – DHW 10°C to 45°C (manufacturer supplied data)
Maximum central heating output	33 kW at 85°C – Htg 50°C to 70°C (manufacturer supplied data) 9.3 kW at 55°C – Htg 33°C to 38°C (manufacturer supplied data)
Maximum primary supply temperature	85°C
Recommended minimum DP	120 kPa
Maximum working pressure primary side	16 bar
Maximum working pressure DHW side	10 bar
Safety relief valve setting secondary heating side	3 bar
Expansion vessel capacity	7 Lt
Ball valve connections	1" male flat seal connection with adaptors down to ¾" male BSP
Safety relief valve connection	¾" Female connection
Electrical power supply voltage	230 V AC±10%
Frequency	50/60 Hz

Table 2 gives a component list for the HIU as supplied by the Client. Items in bold have been changed since the original test covered in [BSRIA Report 101924/1](#).

**Table 2 HIU component list**

Description	Manufacturer
Software version	1961SAT.LO1.00 – C00430823_01
Space heating heat exchanger	SWEP E8AS W-Nx10
<b>DHW heat exchanger</b>	<b>Zilmet 17CA314030 No, plates 40</b>
DHW flowmeter	Honeywell C7195 -0,7-30 l/m'
Check Valve on DCW inlet	Lovato code 20313113
Check Valve on filling circuit	Kramer
Temperature sensors	Brahama G 1/8"-ST06
Primary side strainer	M-M ¾" – VALBRASS
Controller for DHW and Space Heating	Brahama 1961 SAT
Control valve and actuator for space heating and DHW	Jonson control M30X1,5 VA 7481-0003
Heat Meter	Ista Ultego III smart
Differential pressure control valve	Frese Optima compact DN15
Circulation pump	WILO pump block PARA 15/7
Safety valve	Female 3/4"3 bar PINTOSSI +C SPA
Air vent valve	Manual 3/8" – MARVIT SPA
Digital pressure transducer	ELTEK 10.80.40.00.07
Expansion Vessel	Zilio Industries VRP204-7
Isolation valves	Arpro EPP 60 g/L
Pipes	Silmet / Feinrohren
o-ring	Teknofluor – EPDM 70
Joints and connections gasket	Flat seat and nuts-AFM34

Figure 1 shows the TI45 UL (Ultra Lean Electronic HIU) installed in the test rig with the cover removed. A picture of the name plate is also included.

**Figure 1 TI45 UL (Ultra Lean Electronic HIU), installed in the test rig**







Figure 2 shows the TI45 UL (Ultra Lean Electronic HIU), installed in the test rig with the cover on.

**Figure 2 TI45 UL (Ultra Lean Electronic HIU), cover on**



## 3 APPROACH

### 3.1 ABBREVIATIONS

The abbreviations given in Table 3 are used throughout this report.

**Table 3 Abbreviations used**

Abbreviation	Parameter	Units
DH	District Heating	-
SH	Space Heating	-
CWS	Cold Water Supply	-
P <sub>1</sub>	Heat load – primary side	[kW]
P <sub>2</sub>	Heat load – space heating system	[kW]
P <sub>3</sub>	Heat load – domestic hot water	[kW]
t <sub>10</sub>	Temperature at DH supply upstream of 9m HIU supply pipework	[°C]
t <sub>11</sub>	Temperature – primary side flow connection	[°C]
t <sub>12</sub>	Temperature – primary side return connection	[°C]
t <sub>21</sub>	Temperature – space heating system return connection	[°C]
t <sub>22</sub>	Temperature – space heating system flow connection	[°C]
t <sub>31</sub>	Temperature – cold water supply	[°C]
t <sub>32</sub>	Temperature – domestic hot water flow from HIU	[°C]
q <sub>1</sub>	Volume flow – primary side	[l.s <sup>-1</sup> ]
q <sub>2</sub>	Volume flow – space heating system	[l.s <sup>-1</sup> ]
q <sub>3</sub>	Volume flow – domestic hot water	[l.s <sup>-1</sup> ]
Δp <sub>1</sub>	Primary pressure drop across entire HIU unit	[bar]
Δp <sub>2</sub>	Pressure drop – space heating system across HIU	[bar]
Δp <sub>3</sub>	Pressure drop – domestic hot water across HIU	[bar]
VWART <sub>DHW</sub>	DHW Volume Weighted Average Return Temperature	[°C]
VWART <sub>SH</sub>	Space Heating Volume Weighted Average Return Temperature	[°C]
VWART <sub>KWM</sub>	Keep-warm Volume Weighted Average Return Temperature	[°C]
VWART <sub>HEAT</sub>	Annual Volume Weighted Average Return Temperature for Heating Period	[°C]
VWART <sub>NONHEAT</sub>	Annual Volume Weighted Average Return Temperature for Non-Heating	[°C]
VWART <sub>HIU</sub>	Total Annual Volume Weighted Return Temperature	[°C]
SH <sub>PROP</sub>	Annual Heating Period	-
NSH <sub>PROP</sub>	Annual Non-Space Heating Period	-
DH	District Heating (primary) circuit	-
SH	Space Heating circuit	-
CWS	Cold Water Supply	-
DHW	Domestic Hot Water	-
TMV	Thermostatic Mixing Valve	-
TRV	Temperature Regulating Valve	-
UFH	Under Floor Heating	-

## 3.2 INSTRUMENTATION USED

Table 4 shows details of the instrumentation used for the tests.

**Table 4 Instrumentation used**

Instrument	Manufacturer	Range	Units	ID No.	Calibration Due
Keysight logging system	Keysight	-1 – 90	°C	1595 1597	03-09-22
Static pressure transducer DHW circuit – Pressure test Primary circuit for all thermal tests	Fuji Electric	0 – 10	Bar	1592	10-05-22
Static pressure transducer SH circuit – Pressure test Secondary circuit for all thermal tests	Fuji Electric	0 – 10	Bar	1593	10-05-22
Platinum Resistance Thermometers (PRTs)* Used for measuring the inlet/outlet parameters during the testing	TC Ltd	5 – 90	°C	1685	02-12-22
Platinum Resistance Thermometer (PRT)	Anville Sensors Ltd	5 – 90	°C	1685	02-12-22
Flowmeter – DH circuit Space heating tests – (1a – 1f)	Siemens	0 – 0.07	l.s <sup>-1</sup>	2961	21-01-21**
Flowmeter – SH circuit Space heating tests – (1a – 1d)	Siemens	0 – 0.07	l.s <sup>-1</sup>	1678	28-04-21**
Flowmeter – SH circuit Space heating tests – (1f)	Danfoss	0 – 0.2	l.s <sup>-1</sup>	94	27-04-21**
Flowmeter – DH circuit Dynamic tests – (2a and 2b) DHW response time tests (5a & 5b)	Siemens	0 – 0.5	l.s <sup>-1</sup>	2063	12-11-22
Flowmeter – DHW circuit Dynamic tests – (2a and 2b)	Danfoss	0 – 0.2	l.s <sup>-1</sup>	94	10-05-22
Flowmeter – DH circuit Keep warm tests (4a & 4b)	Siemens	0 – 0.07	l.s <sup>-1</sup>	1678	07-05-22
Flowmeter – DHW circuit Keep warm tests (4a & 4b) DHW response time tests (5a & 5b)	Danfoss	0 – 0.2	l.s <sup>-1</sup>	94	10-05-22
Differential pressure transducer DH circuit for all tests except 4b and 5b	Fuji Electric	0 – 200	kPa	2065	08-02-22
Differential pressure transducer SH and DHW circuit for all tests except 4b and 5b DH circuit for tests 4b and 5b	Fuji Electric	0 – 200	kPa	1591	10-05-22
Differential pressure transducer DHW circuit for tests 4a and 4b	Fuji Electric	0 – 50	kPa	1583	10-05-22
Static pressure transducer Pressure test and heating/DHW circuits	Fuji Electric	0 – 30	barg	1582	14-06-22
Stopwatch	RS		Secs	2955	01-12-21
Tape measure	Stanley	1,000	mm	683	28-02-22
Voltage and power draw	Yokogawa	0-300V 0-25W	V/W	988	27-10-22

\*The time constant for these temperature sensors was  $\leq 1.5$  s.

\*\*These tests were carried out in July 2020.

The calibration certificates for all the instrumentation used during this series of tests are available on request from BSRIA (test@BSRIA.co.uk)

Figure 3 shows a schematic of the space heating pipework.

**Figure 3 Schematic of the space heating pipework.**





Figure 4 shows a schematic of the DHW pipework.

**Figure 4 Schematic of the DHW pipework.**



### 3.3 UNCERTAINTY BUDGET

The uncertainty of measurement given in the test regime is shown in Table 5.

**Table 5 Uncertainty budget**

Parameter	Required Uncertainty	BSRIA Uncertainty
Static pressure	±10 kPa	±0.65 kPa
Differential pressure, district heating	<i>Not supplied</i>	±0.06 kPa
Differential pressure, domestic hot water	±1 kPa	±0.06 kPa
Differential pressure, space heating	±1 kPa	±0.06 kPa
Temperature	±0.1°C	±0.02°C
Volume flow (≥ 0.06 l/s)	±1.5%	±0.0006 l/s
Volume flow (< 0.06 l/s)	To be specified in conjunction with each measurement	±0.0007 l/s

The uncertainty of the instrumentation used was calculated according to M3003 – The Expression of Uncertainty and Confidence in Measurement. All the instrumentation used in this series of tests was within the required uncertainty quoted above.



### 3.4 RANGE OF TESTS

Table 6 shows the setup of the tests as given in the test regime.

**Table 6 Test setup as given in the test regime**

Test No.	Test	Static pressure on return	dP across HIU	Primary flow temp	Hot water setpoint	DHW flow rate	DHW power	Space heat output	Space heat flow temp	Space heat return temp
		bar	bar	°C	°C	l/s	kW	kW	°C	°C
			dP <sub>1</sub>	t <sub>11</sub>	t <sub>32</sub>	q <sub>3</sub>	P <sub>3</sub>	P <sub>2</sub>	t <sub>22</sub>	t <sub>21</sub>
<b>Static tests</b>										
0a	Static pressure test (same static pressure on both flow and return connections)	1.43 times rated value		70	50	-	-	-	n/a	n/a
1a	Space Heating 1 kW	3.0	0.5	70	55	-	-	1	60	40
1b	Space Heating 2 kW	3.0	0.5	70	55	-	-	2	60	40
1c	Space Heating 4 kW	3.0	0.5	70	55	-	-	4	60	40
1d	Space Heating 1 kW	3.0	0.5	60	50	-	-	1	45	35
1e	Space Heating 2 kW	3.0	0.5	60	50	-	-	2	45	35
1f	Space Heating 4 kW	3.0	0.5	60	50	-	-	4	45	35
<b>Dynamic tests</b>										
2a	DHW only DH 70°C flow	3.0	0.5	70	55	see DHW test profile	see DHW test profile	-	60	-
2b	DHW only DH 60°C flow	3.0	0.5	60	50			-	45	-
3a	Low flow DHW, DH 70°C flow	3.0	0.5	70	55	0.02	Record value	-	60	-
3b	Low flow DHW, DH 60°C flow	3.0	0.5	60	50	0.02	Record value	-	45	-
4a	Keep-warm, DH 70°C flow	3.0	0.5	70	55	0	0	-	60	-
4b	Keep-warm, DH 60°C flow	3.0	0.5	60	50	0	0	-	45	-
5a	DHW response time	3.0	0.5	70	55	0.13	Record value	-	60	-
5b	DHW response time	3.0	0.5	60	50	0.13	Record value	-	45	-

Table 7 shows the reporting structure of the tests as given in the test regime. A summary of findings is shown in the right hand column, see section 4 for the full test results.

**Table 7 Test reporting structure as given in the test regime**

Test	Description	Reporting	Pass/Fail
<b>Static Tests</b>			
0	Pressure tests	Pass/Fail as to whether HIU manages pressure test without leaks or damage.	Pass
1a	Space Heating 1 kW, 60/40°C secondary	t <sub>11</sub> -primary flow temperature t <sub>12</sub> -primary return temperature.	N/A
1b	Space Heating 2 kW, 60/40°C secondary	Plot of key metrics over duration of test. <b>Note:</b> Outputs used as input data to 'High Temperature' Space Heating Volume Weighted Average Return Temperature calculation.	N/A
1c	Space Heating 4 kW, 60/40°C secondary		N/A
1d	Space Heating 1 kW, 45/35°C secondary	t <sub>11</sub> -primary flow temperature t <sub>12</sub> -primary return temperature	N/A
1e	Space Heating 2 kW, 45/35°C secondary	Plot of key metrics over duration of test. <b>Note:</b> Outputs used as input data to 'Low Temperature' Space Heating Volume Weighted Average Return Temperature calculation.	N/A
1f	Space Heating 4 kW, 45/35°C secondary		N/A
<b>Dynamic Tests</b>			
2a	DHW only, DH 70°C flow; 55°C DHW	Pass/Fail on DHW (at t <sub>32</sub> ) exceeding 65.0°C (to 1 decimal point) for more than 10 consecutive seconds. State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Assessment of scaling risk as per criteria detailed in 2.26. <b>Note:</b> Outputs used as input data to 'High Temperature' Domestic Hot Water Weighted Average Return Temperature calculation. Plot t <sub>32</sub> , t <sub>31</sub> , q <sub>3</sub> , t <sub>12</sub> q <sub>1</sub>	Pass
2b	DHW only, DH 60°C flow; 50°C DHW	State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Plot t <sub>32</sub> , t <sub>31</sub> , q <sub>3</sub> , t <sub>12</sub> q <sub>1</sub> <b>Note:</b> Outputs used as input data to 'Low Temperature' Domestic Hot Water Weighted Average Return Temperature calculation.	N/A
3a	Low flow DHW, DH 70°C flow; 55°C DHW	Pass/Fail on DHW (at t <sub>32</sub> ) exceeding 65.0°C (1 decimal place) for more than 10 consecutive seconds. Comment on ability to deliver DHW at low flow based on DHW temperature reaching at least 45.0°C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on ability to deliver stable DHW flow temperature (at t <sub>32</sub> ) , defined as ability to maintain 55.0 +/-3.0°C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/-°C variance around 55.0°C (1 decimal place) to be stated. Assessment of scaling risk as per criteria detailed in 2.26. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.	Pass

3b	Low flow DHW, DH 60°C flow; 50°C DHW	<p>Comment on ability to deliver DHW at low flow rate based on DHW temperature reaching at least 45°C (one decimal place) at the end of the 180 second period of low flow DHW. Comment on ability to deliver stable DHW flow temperature (at <math>t_{32}</math>), defined as ability to maintain 50.0 +/-3°C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/-°C variance around 50.0°C (1 decimal place) to be stated.</p> <p>Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.</p> <p>Maximum temperature achieved and +/-°C variance around 50.0°C (1 decimal place) to be stated.</p>	N/A
4a	Keep-warm, DH 70°C flow; 55°C DHW	<p>Assessment of whether valid keep-warm operation, based on 5a response time criteria: Pass / Fail.</p> <p>Observation on the operation of the HIU during keep-warm.</p> <p>Assessment of scaling risk, based on duration of temperatures in excess of 55.0°C (one decimal place). Plot temperature <math>t_{10}</math>.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Plot of key metrics over duration of test.</p> <p>State average heat load for the duration of the test.</p> <p>State average primary flowrate for the duration of the test.</p> <p><b>Note:</b> Outputs used as input data to 'High Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p>	Pass
4b	Keep-warm, DH 60°C flow; 50°C DHW	<p>Assessment of whether valid keep-warm operation, based on 5b response time criteria: Pass / Fail.</p> <p>Observation on the operation of the HIU during keep-warm.</p> <p>Assessment of scaling risk, based on duration of temperatures in excess of 55.0°C (one decimal place).</p> <p>Plot temperature <math>t_{10}</math>.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Plot of key metrics over duration of test.</p> <p>State average heat load for the duration of the test.</p> <p>State average primary flowrate for the duration of the test.</p> <p><b>Note:</b> Outputs used as input data to 'Low Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p>	Pass
5a	DHW response time, DH 70°C flow; 55°C DHW	<p>Pass/Fail on DHW (at <math>t_{32}</math>) exceeding 65.0°C (1 decimal place) for more than 10 consecutive seconds. State time to achieve a DHW temperature 45.0°C (1 decimal place) and not subsequently drop below 42.0°C (1 decimal place).'</p> <p>Plot <math>t_{32}</math>, <math>t_{31}</math>, <math>q_3</math>, <math>t_{12}</math>, <math>q_1</math> over duration of test.</p>	Pass
5b	DHW response time, DH 60°C flow; 50°C DHW	<p>Pass/Fail on DHW (at <math>t_{32}</math>). State time to achieve a DHW temperature 45.0°C (1 decimal place) and not subsequently drop below 42.0°C (1 decimal place).</p> <p>Plot <math>t_{32}</math>, <math>t_{31}</math>, <math>q_3</math>, <math>t_{12}</math>, <math>q_1</math> over duration of test.</p>	Pass

## 4 TEST PROCEDURE

The average deviation of  $t_{31}$  (CWS) during test 2a, 2b, 3a,3b, 5a and 5b remained within  $\pm 0.5^{\circ}\text{C}$  of the stipulated  $10^{\circ}\text{C}$  as required by the test regime (see paragraph 2.11 of the test regime).

### 4.1 TESTS 1A TO 1F

Once the rig was running, the space heating tests were allowed to stabilise at the required power output for the particular test. Once stable conditions had been achieved, the test was logged at a rate of 1 Hz for a minimum period of 300 seconds.

### 4.2 TESTS 2A AND 2B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW draw off test was carried out as per the flow regime specified in the test method. The flow rates were controlled using a manifold of three control valves set to the correct flows. The data was logged at a rate of 1 Hz.

### 4.3 TESTS 3A AND 3B

Prior to the tests being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW flow was reduced to 0.02 l/s as required by the test regime and logged for 180 seconds at a rate of 1 Hz.

### 4.4 TESTS 4A AND 4B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW flow was turned off and left for a minimum of 8 hours to establish “keep warm” conditions. The keep warm mode for this HIU was a trickle flow through the primary circuit. During this test, the primary flow was diverted through a DN3 flowmeter so that the trickle flow could be measured. The data was logged at a rate of 1 Hz throughout the duration of the 8-hour test period.

### 4.5 TESTS 5A AND 5B

These tests were carried out while the HIU was still in “keep warm” mode after the 8-hour keep warm test. With the data still being logged at a rate of 1 Hz, the DHW flow was immediately brought back to 0.13 l/s.

## 5 TEST RESULTS

During all the tests, the ambient temperature within the vicinity of the HIU being tested was within the tolerance of 20°C ±5°C as specified in the test regime. Charts of the key metrics for the thermal tests are given in Appendix A.

### 5.1 PRESSURE TEST – 0A

The DHW circuit and the space heating circuit were pressurised to 1.5 bar. The primary circuit was pressurised to 1.43 times the rated maximum static pressure of 16 bar (test pressure 22.88bar). This pressure was held for 30 minutes. After the 30-minute test period, the connections and fittings on the HIU were inspected for leaks and any signs of deformation. During the 30-minute period, there were no leaks or signs of deformation.

Result – Pass.

### 5.2 STATIC TESTING – 1A, 1B, 1C, 1D, 1E AND 1F

The space heating tests results in this report are taken from the original testing detailed in [BSRIA Report 101924/1](#).

- 1a – DH inlet 70°C, heating return at 40°C and a flow set to achieve 1kW heating duty
- 1b – DH inlet 70°C, heating return at 40°C and a flow set to achieve 2kW heating duty
- 1c – DH inlet 70°C, heating return at 40°C and a flow set to achieve 4kW heating duty
- 1d – DH inlet 60°C, heating return at 35°C and a flow set to achieve 1kW heating duty
- 1e – DH inlet 60°C, heating return at 35°C and a flow set to achieve 2kW heating duty
- 1f – DH inlet 60°C, heating return at 35°C and a flow set to achieve 4kW heating duty

For tests 1a to 1c, the space heating outlet temperature was set to 59°C in the HIU control software to achieve 60°C (±0.5°C) during the 4kw test. The For tests 1d to 1f, the space heating outlet temperature was set to 45°C in the HIU control software to achieve 45°C (±0.5°C) during the 4kw test. Table 8 shows a summary of the results for the static tests. Table 9 shows the uncertainty of measurement for the space heating tests.

**Table 8 Results from the static tests**

Test	District Heating Circuit					Space Heating Circuit			
	t <sub>11</sub> (°C)	t <sub>12</sub> (°C)	q <sub>1</sub> (l/s)	Δp <sub>1</sub> (kPa)	P <sub>1</sub> (kW)	T <sub>21</sub> (°C)	T <sub>22</sub> (°C)	q <sub>2</sub> (l/s)	P <sub>2</sub> (kW)
1a	69.99	42.49	0.010	50.60	1.14	39.73	61.66	0.011	0.99
1b	70.04	43.87	0.019	50.94	2.06	39.94	60.93	0.023	1.98
1c	70.10	45.28	0.039	50.70	4.01	39.99	59.77	0.048	3.90
1d	59.93	36.26	0.012	50.67	1.18	35.10	48.33	0.020	1.09
1e	60.19	35.80	0.019	50.41	1.93	35.00	43.10	0.057	1.91
1f	60.24	37.44	0.043	51.25	4.07	35.20	45.01	0.098	3.98

**Table 9 Uncertainty budget for tests 1a to 1f**

Test	Uncertainty Budget District Heating Circuit					Uncertainty Budget Space Heating Circuit			
	t <sub>11</sub> (°C)	t <sub>12</sub> (°C)	q <sub>1</sub> (l/s)	Δp <sub>1</sub> (kPa)	P <sub>1</sub> (kW)	T <sub>21</sub> (°C)	T <sub>22</sub> (°C)	q <sub>2</sub> (l/s)	P <sub>2</sub> (kW)
1a to 1e	±0.018	±0.018	±0.0006	0.031	±0.06	±0.018	±0.018	±0.0006	±0.06
1f	±0.018	±0.018	±0.0006	0.031	±0.06	±0.018	±0.018	±0.0007	±0.04

## 5.3 DYNAMIC TESTING OF THE HIU OPERATION – 2A AND 2B

### 5.3.1 Test 2a

Test 2a was carried out with the DH water temperature set to 70°C and the cold-water supply to the DHW circuit at 10°C. The DHW outlet temperature in the HIU control software was set to 58°C to achieve 55.0°C ( $\pm 0.5^\circ\text{C}$ ) at a DHW flow rate of 0.130 l/s, prior to the test.

During test 2a:

- The DHW temperature did not exceed 65°C at any point during the test
- The maximum DHW temperature was 58.2°C
- The minimum DHW temperature was 49.9°C
- Details of the scaling risk are given in **Table 10**
- $T_{31}$  (CWS) had an average value of 10.19°C and a standard deviation of 0.07°C

**Result – Pass**

### 5.3.2 Test 2b

Test 2b was carried out with the DH water temperature set to 60°C and the cold-water supply to the DHW circuit at 10°C. The DHW outlet temperature in the HIU control software was set to 52°C to achieve 50.0°C ( $\pm 0.5^\circ\text{C}$ ) at a DHW flow rate of 0.130 l/s, prior to the test.

During test 2b:

- The maximum DHW temperature was 52.9°C
- The minimum DHW temperature was 47.4°C
- $T_{31}$  (CWS) had an average value of 10.16°C and a standard deviation of 0.06°C

**Result – There is no pass/fail criteria for this test.**

## 5.4 LOW FLOW DHW TESTS – 3A AND 3B

### 5.4.1 Test 3a

Test 3a was carried out with the DH water temperature set to 70°C ( $\pm 0.5^\circ\text{C}$ ) and the cold water supply to the DHW circuit at 10°C ( $\pm 0.5^\circ\text{C}$ ). The DHW outlet temperature setpoint remained at the same position, set to achieve 55.0 ( $\pm 0.5^\circ\text{C}$ ) at a DHW flow rate of 0.130 l/s. The low DHW flow rate was reduced to 0.02 l/s as required by the test regime.

During test 3a:

- The DHW temperature did not exceed 65°C at any point during the test
- The HIU was able to deliver DHW above 45°C at the end of the 180 second test
- During the last 60 seconds of the test the DHW temperature averaged 53.8°C and ranged from 55.7°C to 51.6°C so the results were not within the stated tolerance of 55.0°C  $\pm 3^\circ\text{C}$  during this time period.
- The DHW maximum and minimum outlet temperatures were 58.8°C and 49.3°C respectively during the 180 second test.
- $T_{31}$  (CWS) had an average value of 10.02°C and a standard deviation of 0.04°C
- Details of the scaling risk are given in **Table 10**

**Result – Pass**

### 5.4.2 Test 3b

Test 3b was carried out with the DH water temperature set to 60°C ( $\pm 0.5^\circ\text{C}$ ) and the cold water supply to the DHW circuit at 10°C ( $\pm 0.5^\circ\text{C}$ ). The DHW outlet temperature setpoint remained at the same position, set to achieve 50.0 ( $\pm 0.5^\circ\text{C}$ ) at a DHW flow rate of 0.130 l/s. The low DHW flow rate was reduced to 0.02 l/s as required by the test regime.

During test 3b:

- The HIU was able to deliver DHW above 45°C at the end of the 180 second test
- During the last 60 seconds of the test the DHW temperature averaged 48.3°C and ranged from 48.9°C to 47.6°C so the results were within the stated tolerance of 50.0°C  $\pm 3^\circ\text{C}$  during this time period.
- The DHW maximum and minimum outlet temperatures were 52.6°C and 43.3°C respectively during the 180 second test.
- T<sub>31</sub> (CWS) had an average value of 10.09°C and a standard deviation of 0.03°C

**Result – There is no pass/fail criteria for this test.**

## 5.5 KEEP WARM TESTS – 4A AND 4B

The keep warm function was a pulsed flow on the DH circuit as can be seen on the charts in Appendix A.

### 5.5.1 Test 4a

Test 4a was carried out with the DH water temperature set to 70°C ( $\pm 0.5^\circ\text{C}$ ) and the cold water supply to the DHW circuit at 10°C ( $\pm 0.5^\circ\text{C}$ ). The DHW outlet temperature setpoint remained at the same position, set to achieve 55.0 ( $\pm 0.5^\circ\text{C}$ ) at a DHW flow rate of 0.130 l/s. The HIU was running at these conditions for at least 2 minutes before this test was carried out.

Once the keep warm function had stabilised (approximately 10,000 seconds into the test), the average  $t_{11}$  temperature for the remainder of the test (18,800 seconds) was 47.0°C varying between 46.1°C and 48.43°C. The average  $t_{12}$  temperature during this same period was 40.9°C varying between 39.0°C and 42.9°C.

During test 4a:

- The average heat load during the 8-hour keep warm period was 36 W
- The average primary flow rate during the 8-hour keep warm period was 4.3 l/h
- The average measured voltage was 230.2V
- The average measured electrical power draw was 1.9 W
- Details of the scaling risk are given in Table 10

**Based on the results for the DHW response time during test 5a, the HIU does perform a valid keep warm operation.**

### 5.5.2 Test 4b

Test 4b was carried out with the DH water temperature set to 60°C ( $\pm 0.5^\circ\text{C}$ ) and the cold water supply to the DHW circuit at 10°C ( $\pm 0.5^\circ\text{C}$ ). The DHW outlet temperature setpoint remained at the same position, set to achieve 50.0 ( $\pm 0.5^\circ\text{C}$ ) at a DHW flow rate of 0.130 l/s. The HIU was running at these conditions for at least 2 minutes before this test was carried out.

Once the keep warm function had stabilised (approximately 12,000 seconds into the test), the average  $t_{11}$  temperature for the remainder of the test (16,800 seconds) was 46.2°C varying between 45.7°C and 47.1°C. The average  $t_{12}$  temperature during this same period was 42.6°C varying between 41.3°C and 43.7°C.

- The average heat load during the 8-hour keep warm period was 34 W
- The average primary flow rate during the 8-hour keep warm period was 6.1 l/h
- The average measured voltage was 230.0V
- The average measured electrical power draw was 1.9 W
- Details of the scaling risk are given in Table 10

**Based on the results for the DHW response time during test 5b, the HIU does perform a valid keep warm operation.**



## 5.6 DHW RESPONSE TIME – 5A AND 5B

### 5.6.1 Test 5a

Test 5a was carried out immediately after test 4a with all the settings and conditions the same. The DHW isolation valve was opened to achieve 0.130 l/s instantly.

During test 5a:

- The DHW temperature did not exceed 65.0°C during the test
- The DHW achieved 45.0°C in 11 seconds from the first recorded non-zero DHW flow reading
- The DHW temperature did not subsequently drop below 42.0°C

Not exceeding 65.0°C during the test – Pass

Achieving 45°C DHW within 15 seconds – Pass

DHW temperature not subsequently dropping below 42.0°C – Pass

**Overall result – Pass**

### 5.6.2 Test 5b

Test 5b was carried out immediately after test 4b with all the settings and conditions the same. The DHW isolation valve was opened to achieve 0.130 l/s instantly.

During test 5b:

- The DHW achieved 45.0°C in 14 seconds from the first recorded non-zero DHW flow reading
- The DHW temperature did not subsequently drop below 42.0°C

Achieving 45°C DHW within 15 seconds – Pass

DHW temperature not subsequently dropping below 42.0°C – Pass

**Overall result – Pass**

## 5.7 TOTAL SCALING RISK ASSESSMENT

The scaling risk criteria is given in section 2.26 of the test regime. Table 10 gives details of the scaling risk associated with this HIU. If any of the factors given in Table 10 occur, then there is an increased scaling risk of the DHW plate in hard water areas.

**Table 10 Total scaling risk assessment**

Has the HIU got a TMV or TRV on the output of the DHW plate heat exchanger?	No	
	Test	
	2a	3a
t <sub>32</sub> above 60°C for more than 5 seconds	No	No
t <sub>12</sub> exceeds 55°C at any point of the test	No	No
	4a	4b
t <sub>12</sub> exceeds 50°C at any time	No	<b>No</b>

## 5.8 VOLUME WEIGHTED AVERAGE RETURN TEMPERATURE

The Volume Weighted Average Return Temperature (VWART) results are given in Appendix B.

**APPENDIX A: DATA CHARTS**

Figure 5 Results for test 1a: 1kW Space heating – DH 70°C supply




Figure 6 Results for test 1b: 2kW Space heating – DH 70°C supply




Figure 7 Results for test 1c: 4kW Space heating – DH 70°C supply




Figure 8 Results for test 1d: 1kW Space heating – DH 60°C supply




Figure 9 Results for test 1e: 2kW Space heating –DH 60°C supply






Figure 10 Results for test 1f: 4kW Space heating – DH 60°C supply




Figure 11 Results for test 2a: DHW dynamic test – DH 70°C supply




Figure 12 Results for test 2b: DHW dynamic test – DH 60°C supply




Figure 13 Results for test 3a: Low flow DHW test – DH 70°C supply




Figure 14 Results for test 3b: Low flow DHW test – DH 60°C supply






Figure 15 Results for test 4a: Keep warm test – DH 70°C supply




— t10 (Line inlet)     
 — t11 (DH supply)     
 — t12 (DH return)     
 — t31 (CWS)  
— t32 (DHW supply)     
 ••••• q1 (DH)     
 ••••• q3 (DHW)

Figure 16 Results for test 4b: Keep warm test – DH 60°C supply




— t10 (Line inlet)     
 — t11 (DH supply)     
 — t12 (DH return)     
 — t31 (CWS)  
— t32 (DHW supply)     
 ••••• q1 (DH)     
 ••••• q3 (DHW)

Figure 17 Results for test 5a: DHW response time – DH 70°C supply





**Figure 18 Results for test 5b: DHW response time – DH 60°C supply**



## APPENDIX B: VWART CALCULATIONS

High Temperature V<sub>W</sub>ART Calculations



**High Temperature V<sub>W</sub>ART Calculation for Rhico District Heating Products**

Primary flow temperature = 70°C, DHW set point = 55°C, Space heating temperatures = 40°C/60°C

Test carried out by BSRIA Ltd. in December 2021/February 2022, Test Reference 102787/1

Manufacturer: Rhico District Heating Products; Model: TI45 UL (Ultra Lean Electronic HIU); Serial number: 428440300/Matr.: A202800460/1; Year of manufacture: 2020

V<sub>W</sub>ART calculation prepared by Colin Judd of BSRIA Ltd. on 28 January 2022

	V <sub>W</sub> ART (°C)	Volume (m <sup>3</sup> )
<b>DHW</b>	15	22.8
<b>Keep Warm</b>	40	34.6
<b>Space Heating</b>	44	50.6

V <sub>W</sub> ART with keep warm active		
Period	V <sub>W</sub> ART (°C)	% Time
<b>No Heating</b>	30	93%
<b>Heating</b>	43	7%
<b>Overall</b>	31	

	DHW draw test results			Post DHW draw (60 Seconds)	
	Power (W)	Primary Flow (m <sup>3</sup> /hr)	Return Temp (V <sub>W</sub> ART) (°C)	Primary Flow (m <sup>3</sup> /hr)	Return Temp (V <sub>W</sub> ART) (°C)
Low	11074	0.166	13.7	0.002	13.58
Medium	18880	0.299	15.2	0.004	14.73
High	24655	0.390	15.9	0.002	15.47

DHW draw volumes per annum		
Energy (kWh)	Time (Hours)	Volume (m <sup>3</sup> )
729	65.83	10.901
297	15.73	4.696
444	18.01	7.022

Post DHW draw volumes per annum		
Events	Avg duration (Seconds)	Volume (m <sup>3</sup> )
10000	30	0.138
660	75	0.059
300	145	0.022

Keep warm test results	
Primary Flow (m <sup>3</sup> /hr)	Return Temp (V <sub>W</sub> ART) (°C)
0.0043	40.2

Keep Warm volumes per annum	
Time (Hours)	Volume (m <sup>3</sup> )
8024	34.588

	Space Heating Test Results		
	Power (W)	Primary Flow (m <sup>3</sup> /hr)	Return Temp (V <sub>W</sub> ART) (°C)
1kW	1009	0.036	42.5
2kW	1984	0.068	43.9
4kW	3974	0.140	45.3

Space Heating volumes per annum		
Energy (kWh)	Time (Hours)	Volume (m <sup>3</sup> )
98	97.16	3.498
787	396.70	27.134
565	142.17	19.961

Low Temperature VVART Calculations



**Low Temperature VVART Calculation for Rhico District Heating Products**

Primary flow temperature = 60°C, DHW set point = 50°C, Space heating temperatures = 35°C/45°C

Test carried out by BSRIA Ltd. in December 2021/February 2022, Test Reference 102787/1

Manufacturer: Rhico District Heating Products; Model: TI45 UL (Ultra Lean Electronic HIU); Serial number: 428440300/Matr.: A202800460/1; Year of manufacture: 2020

VVART calculation prepared by Colin Judd of BSRIA Ltd. on 08 February 2022

	VVART (°C)	Volume (m <sup>3</sup> )
<b>DHW</b>	16	28.7
<b>Keep Warm</b>	41	49.3
<b>Space Heating</b>	37	53.8

VVART with keep warm active		
Period	VVART (°C)	% Time
<b>No Heating</b>	32	93%
<b>Heating</b>	36	7%
<b>Overall</b>	32	

	DHW draw test results			Post DHW draw (60 Seconds)	
	Power (W)	Primary Flow (m <sup>3</sup> /hr)	Return Temp (VVART) (°C)	Primary Flow (m <sup>3</sup> /hr)	Return Temp (VVART) (°C)
Low	9807	0.183	14.5	0.003	14.46
Medium	16672	0.330	16.1	0.003	15.86
High	21893	0.437	16.9	0.006	16.61

DHW draw volumes per annum		
Energy (kWh)	Time (Hours)	Volume (m <sup>3</sup> )
729	74.33	13.580
297	17.81	5.873
444	20.28	8.857

Post DHW draw volumes per annum		
Events	Avg duration (Seconds)	Volume (m <sup>3</sup> )
10000	30	0.251
660	75	0.043
300	145	0.073

Keep warm test results	
Primary Flow (m <sup>3</sup> /hr)	Return Temp (VVART) (°C)
0.0061	41.2

Keep Warm volumes per annum	
Time (Hours)	Volume (m <sup>3</sup> )
8011	49.256

	Space Heating Test Results		
	Power (W)	Primary Flow (m <sup>3</sup> /hr)	Return Temp (VVART) (°C)
1kW	1106	0.043	36.3
2kW	1930	0.069	35.8
4kW	4038	0.156	37.4

Space Heating volumes per annum		
Energy (kWh)	Time (Hours)	Volume (m <sup>3</sup> )
98	88.64	3.825
787	407.72	28.117
565	139.93	21.839

## APPENDIX C: CERTIFICATE OF CONFORMITY SUPPLIED BY THE CLIENT



---

### Declaration of Conformity EU

---

Produttore: Lovato S.P.A

Indirizzo: Via Selva 4/A, 37040 Gazzolo d'Arcole (VR)

### DECLARES

on its own responsibility that the **TI45 Ultra Lean** equipment is constructed in accordance with the directives:

- 2014/30 /UE (direttiva EMC)
- 2014/35/UE (direttiva LVD)
- 2011/65/UE (direttiva RoHS2)

The company Lovato S.p.A. also declares that the following standards have been applied for the design and construction verification of the equipment:

- EN61010-1:2010/A1:2019
- EN 55014-1:2017-04
- EN 55014-2:2015-04
- EN 60335-1:2019-10

The technical documentation proving compliance with legal requirements is kept at our premises in Gazzolo d'Arcole, Via Selva 4/a.

Il rappresentante legale

Lovato Michele

A handwritten signature in black ink, appearing to read "Michele Lovato".

Gazzolo d'Arcole  
data 18/01/2021



---

**Declaration of Incorporation for partly completed machinery**  
Machinery Directive 2006/42/CE, Annex II., B

---

Manufacturer: *Lovato S.P.A*  
Address: *Via Selva 4/A, 37040 Gazzolo d'Arcole (VR)*

Name and address of the person authorised to compile the relevant technical documentation.

Name : *Lovato S.P.A.*  
Address: *Via Selva 4/A, 37040 Gazzolo d'Arcole (VR)*

Declares with the present document that the partly completed machinery:

**HEATING INTERFACE UNIT TI45 Ultra Lean**

- The following essential requirement to the Machinery directive(2006/42/CE) are applied and fulfilled:1.1,1.1.2,1.1.3,1.1.5,1.1.6,1.2.1,1.2.2,1.2.3,1.2.4,1.2.4.1,1.2.4.2,1.2.4.3,1.2.5,1.2.6,1.3.1,1.3.2,1.3.3,1.3.4,1.3.6,1.4.1,1.4.2,1.4.2.1,1.5.1,1.5.5,1.6.1,1.6.5,1.7.3.
- The relevant technical documentation is compiled in accordance with Part B of Annex VII; the documentation or part of it will be sent per post or by e-mail, in response to the specified request by the competent national authorities.
- This partly completed machinery is in compliance with the following CE Directive: 2006/95CE, 2004/108CE
- Electrical safety test is carried out according to the standard EN60335-1

And also declares that the partly completed machinery must not be put into service until the final machinery into which it is to be incorporated has been declared in conformity, where appropriate, with the Machinery Directive 2006/42/CE.

LOVATO S.p.A.  
Lovato Michele  
Chief Executive Officer

Gazzolo d'Arcole  
data 01/03/2020

---

Dichiarazione n. 005